

QUOTATION

pacific truck equipment inc.

1655 e. washington blvd. whittier, ca 90606-2424

562/464-9674 fax 562/464-6067

DATE ENTERED 8/26/2020	CUST. P.O.	TERMS Net 10 ...	TAXABLE YES NO
---------------------------	------------	-----------------------	---------------------

ESTIMATE # 7560

TO	WONDRIES FLEET GROUP 1247 MAIN ST ALHAMBRA CA 91801	DATE REQUESTED 8/26/2020	TRUCK DUE DATE
		BUYER'S NAME JOHN OVIYACH	WRITTEN BY J.K.
		HOW SHIP	
		SPECIFICATIONS	
SHIP TO	CITY OF GARDEN GROVE UNIT# 588	MAKE / MODEL / YEAR / COLOR / C.A DIM FORD, F-550, 84" CA	
		DUAL-SNGL / TIRE SIZE / 4-WHL DR. / PKTS / EXT. CAB DRW CHASSIS	

ITEM	QUAN	DESCRIPTION	UNIT PRICE	Sub Total
A	1	126402054 VF PAINTED WHITE AND INSTALLED	45,423.00	45,423.00
B	1	COMPT. ARRANGEMENT 38-24-40-24	0.00	0.00T
C	1	C.S.#1 COMPT. RAISED 60" H. X 20" D. X 38" W. WITH OXY AND ACE BOTTLE BRACKETS, LOUVERS, HEAVYBOTTOM AND (1) EA OXY AND ACE HOSE REEL SUSPENDED FROM COMPT. TOP WITH 25' OF 1/4" SIAMESE HOSE TO PULL OUT SIDE DOORS	0.00	0.00T
D	1	(2) EA SWIVEL MATERIAL HOOKS IN C.S.#1 COMPT.	0.00	0.00T
E	1	C.S.#2 COMPT. TO HAVE (1) EA 6" D. , (2) 4" D. AND (4) EA 3" D. 250# CAP. ROLLOUT DRAWERS WITH METAL DIVIDERS STACKED FROM THE BOTTOM UP	0.00	0.00T
F	1	C.S. #3 COMPT. TO HAVE (1) EA ADJ. SHELF WITH METAL DIVIDERS	0.00	0.00T
G	1	C.S. #4 COMPT. TO HAVE (1) EA SAMLEX 2000 WATT PURE SINE INVERTER INSTALLED (1) EA AUXILIARY BATTERY AND (3) EA 4" D. 250# CAP ROLLOUT DRAWERS WITH METAL DIVIDERS STACKED FROM THE TOP DOWN	0.00	0.00T
H	1	(2) EA GFI PLUGS INSTALLED (WILL ADVISE LOCATIONS)	0.00	0.00T
I	1	S.S.#1 COMPT. RAISED 60" H. X 20" D. X 38" W. WITH (1) EA 6" D. AND (5) EA 4" D. 250# CAP. ROLLOUT DRAWERS WITH METAL DIVIDERS STACKED FROM THE BOTTOM UP CAPPED OFF WITH A HEAVY FIXED SHELF AND (4) EA SWIVEL MATERIAL HOOKS (2 PER DOOR) INSTALLED.	0.00	0.00T
J	1	S.S. #2 COMPT. TO HAVE (2) EA ADJ. SHELVES	0.00	0.00T
K	1	S.S.#3 COMPT. TO HAVE (1) EA ADJ. SHELF	0.00	0.00T
L	1	S.S.#4 COMPT. TO HAVE (1) EA ADJ. SHELF	0.00	0.00T
M	1	REAR 18" THRU PLATFORM WITH FOLD DOWN DOOR EACH SIDE	0.00	0.00T
N	1	ALUMINUM DIA PLATE COMPT. TOPS	0.00	0.00T
O	1	FURNISH AND INSTALL STRIP LIGHTING WITH PUSH PULL SWITCH IN ALL 10 COMPT. OPENINGS	0.00	0.00T
P	1	(1) EA 12" X 12" VISE PLATE ON C.S. REAR CORNER OF THRU PLATFORM	0.00	0.00T
Q	1	(1) EA WHACKER SECUREMENT SYSTEM ON S.S. OF REAR PLATFORM AGAINST REAR END PANEL	0.00	0.00T
R	1	THE ENTIRE BED AREA, REAR PLATFORM AND REAR CHANNEL STEP SHALL BE SPRAY LINED	0.00	0.00T

Sub Total
Sales Tax
Total

QUOTATION

pacific truck equipment inc.

1655 e. washington blvd. whittier, ca 90606-2424

562/464-9674 fax 562/464-6067

DATE ENTERED 8/26/2020		CUST. P.O.		TERMS Net 10 ...		TAXABLE YES NO		ESTIMATE # 7560
TO WONDRIES FLEET GROUP 1247 MAIN ST ALHAMBRA CA 91801				DATE REQUESTED 8/26/2020		TRUCK DUE DATE		
				BUYER'S NAME JOHN OVIYACH		WRITTEN BY J.K.		
				HOW SHIP				
SHIP TO CITY OF GARDEN GROVE UNIT# 588		SPECIFICATIONS						
		MAKE / MODEL / YEAR / COLOR / C.A DIM FORD, F-550, 84" CA						
		DUAL-SNGL / TIRE SIZE / 4-WHL DR. / PKTS / EXT. CAB DRW CHASSIS						

ITEM	QUAN	DESCRIPTION	UNIT PRICE	Sub Total
S	1	(1) EA CAB PROTECTOR INSTALLED BETWEEN RAISED COMPTS. WITH LIGHTBAR MOUNT	0.00	0.00T
T	1	FURNISH (1) EA WATER CASK BRACKET (LOOSE)	0.00	0.00T
U	1	FABRICATE AND INSTALL (1) EA SIDE TYPE EXP. METAL BASKET FROM REAR OF S.S. RAISED COMPT. TO REAR END PANEL 9 1/2" H. X 10" W. AND SHALL BE FLUSH WITH TOP OF RAISED COMPT.	0.00	0.00T
V	1	L.E.D LEGAL LIGHTS IN REAR FASCIA PANEL	0.00	0.00T
W	1	(1) EA 6 STROBE SYSTEM 2 FRONT, 2 SIDE AND 2 REAR INSTALLED	0.00	0.00T
X	1	6" REAR CHANNEL STEP (SPRAY LINED)	0.00	0.00T
Y	1	10,000# RECEIVER HTICH AND 7 PRONG RV TYPE PLUG	0.00	0.00T
Z	1	(1) EA COMBO PINTLE BALL HITCH # B-82000, SLIDE ADAPTOR AND RETAINER PIN	0.00	0.00T
AA	1	FURNISH AND INSTALL (1) EA CODE 3 LIGHTBAR MODEL# 211F58-C60458 WITH REAR FACING ARROWSTICK INSTALLED ON CAB PROTECTOR WITH #NASLDRL CONTROLLER	0.00	0.00T
BB	1	ALUMINUM GRAVEL GUARDS INSTALLED	0.00	0.00T
CC	1	PAIR OF REAR GRAB HANDLES INSTALLED	0.00	0.00T
DD	1	4 CORNER STROBE SYSTEM INSTALLED	0.00	0.00T
EE	1	BACK UP ALARM INSTALLED	0.00	0.00T
FF	1	5# FIRE EXTINGUISHER	0.00	0.00T
GG	1	EMERGENCY TRIANGLE KIT	0.00	0.00T
HH	1	(1) EA L.E.D. WORK LIGHT INSTALLED IN BED AREA PER SKETCH	0.00	0.00T
II	1	INSTALL FACTORY SUPPLIED BACK UP CAMERA TO O.E.M SYSTEM	0.00	0.00T
NO OTHER ITEMS INCLUDED				

Sub Total	\$45,423.00
Sales Tax	\$0.00
Total	\$45,423.00